HASSAN DIVISION.

Dated 22nd March 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 10th April 1916, for extending and improving the A.-V. School, Channarayapatna. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 12 noon and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for extending and improving the A.-V. School at Channarayapatna," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate quantities of work for constructing A.-V. School at Channarayapatna.

No.	Items of work	Per	Quantity
1	Removing the existing roof with tiles, reepers, etc., and stacking	Sq.	22·00
2	Dismantling masonry walls	C. ft.	1,125
3	Sundry items that may be found necessary during dismantling, etc.	Lump	sum.
4	Earthwork excavating for foundation	C. yd.	87
5	Stone in clay, foundation	C. ft.	2,626
	Do basement	,,	1,079
6	Burnt brick in clay superstructure	,,	4,859
6a	Do in mortar do	,,	982
7	Do arch work	,,	113
8	Burnt stone slabs, dressed, 4" to 6" thick	S. ft.	295
9	Fixing old slabs	,,	151
10	Forming caps and bases of pillars in verandah	Each	8
11	Moulding with pillasters around arches, etc.	Lump	sum.
12	New teakwood pannelled doors with fastenings, etc.	S. ft.	236
13	New teakwood windows with iron bars, iron work and glazed shutters, etc.	,,	63
14	Teakwood circular ventilators with glazed shutters	,,	48
15	Burnt stone slab pillars nicely dressed and grooves cutting and fixed	,,	72
16	Removing and refixing old doors and windows	Each	10
17	Teakwood, wrought and put up complete	C. ft.	267·00
18	Refixing old bressummers and rafters to front verandah	Lump	sum.
19	Stone brackets to support purlins of front verandah	Each	24
20	Roofing with 1st class Mangalore tiles, teak reepers, etc., complete	Sq.	32·30
21	Roofing with old Mangalore tiles, teak reepers, etc., complete	,,	22·00
22	Ridge tiles set in mortar and pointed	R. ft.	80
23	Resetting old ridge tiles in motar and pointed	,,	65
24	Providing zinc sheets and planking for valleys and mortar bands	S. ft.	869
25	Teakwood eave board	R. ft.	366
26	Refixing old eave board	,,	75
27	Teakwood finials	Each	4
28	Do pendants	,,	8
29	Chunam plastering	Sq.	104·40
30	White and colorwashing	,,	104·40
31	Flooring with first class Mangalore tiles, 9" square over 3" concrete bed and cement pointing, complete.	,,	13·00
32	Do with Cuddapah slabs over 3" concrete bed and cement pointing, etc., complete.	,,	4·00
33	Painting doors and windows	,,	22·04
34	Chunam borders over roof	R. ft.	326
35	Front pediment work as per plan	Lump	sum.
36	Repairs to existing building including white and colorwashing and unforeseen items, etc.	Lump	sum.
37	Clearing site and levelling ground and removing high ground in rear, filling ditch in front and forming play ground, etc.	Lump	sum.

K. R. SESHACHAR,
Executive Engineer.